

Traffic Safety Sampler

Deirdre Thompson ~ Will Mathies ~ Mark McCulloch Chuck Bergmann ~ Gary Loyola ~ Kim Lariviere Dean Kanitz ~ Hilary Owen ~ Garrett Dawe ~ Bonnie Wood




Much Ado About Crosswalks?

Deirdre Thompson

MDOT Pedestrian and Bicycle Safety Engineer

Crosswalk?!?!







	# of lanes	# of	Roadway ADT and Posted Speed															
	crossed	multiple	1,500 - 9,000 vpd			9,000 - 12,000 vpd				12,000 - 15,000 vpd				>15,000 vpd				
	to reach	threat	≤30	35	40	≥ 45	≤ 30	35	40	≥45	≤30	35	40	≥ 45	≤ 30	35	40	≥45
Roadway configuration	a refuge	lanes*	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph	mph
2 Lanes (one way street)	2	1	Α	Α	В	D	Α	Α	В	О	Α	Α	В	D	Α	В	В	D
2 Lanes (two way street with no median)	2	0	Α	Α	В	D	Α	Α	В	D	Α	Α	В	D	Α	В	В	D
2 Lanes w/ Raised Median	1	0	Α	Α	В	D	Α	Α	С	D	Α	Α	В	D	Α	С	С	D
3 Lanes (center turn lane)	3	1	В	В	С	D	В	В	С	D	В	В	С	D	В	С	С	D
4 Lanes (two way street with no median)	4	2	Α	С	С	D	Α	С	С	D	Α	С	С	D	С	С	С	D
5 Lanes w/ refuge island or 4 lanes w/raised median	2	2	Α	Α	С	D	Α	В	С	D	Α	В	C	D	В	В	С	D
5 Lanes (center turn lane)	5	2	С	С	С	D	С	С	С	О	С	С	С	D	С	С	С	D
6 lanes (two way street with or without median)	3 to 6	4	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Ε	Е	Е
	1 11 1		,					,									7.51	

- * A multiple threat lane is defined as a through lane where it is possible for a pedestrian to step out in front of a stopped vehicle in the adjacent travel lane (Either through or turn)
- A Install special emphasis marked crosswalk with appropriate signing (See MDOT Traffic Sign Design, Placement and Application Guide). Evaluate need for advanced signing.
- B Install special emphasis marked crosswalk with appropriate signing (See MDOT Traffic Sign Design, Placement and Application Guide) only in conjunction with geometric improvements such as bulb-outs or median refuge islands.
- C Install special emphasis marked crosswalk with appropriate signing (See MDOT Traffic Sign Design, Placement and Application Guide) only in conjunction with geometric improvements. Consider pedestrian activated Rectangular Rapid Flashing Beacons (RRFB) if criteria are met in Figure 2. Submit form 1597 to MDOT Signal Operations to request a study for any electronic pedestrian device.
- Do not install marked crosswalk at uncontrolled crossing. Determine if the speed limit can be effectively reduced to 40 mph and raised median refuge island can be installed. If so, utilize Type C criteria. If this is not possible, or if pedestrian volume falls above the RRFB limit line on Figure 2, consider Pedestrian Hybrid Beacon (PHB), pedestrian traffic signal or grade separated crossing. Specific Guidance: Evaluation of the PHB, pedestrian traffic signal or grade separation treatments must consider corridor signal progression, existing grades, physical constraints and other engineering factors. Submit form 1597 to MDOT signal operations to request a study for any electronic pedestrian device.
- Do not install marked crosswalk at uncontrolled crossing with 3 or more through lanes per direction or where the speed limit is ≥ 45 mph and there is not a median refuge on a 5-lane crossing. Do not consider the use of pedestrian activated RRFB's. Consider PHB, pedestrian traffic signal or grade separated crossing.

 Specific Guidance: Evaluation of the PHB, pedestrian traffic signal or grade separation treatments must consider corridor signal progression, existing grades, physical constraints and other engineering factors. Submit form 1597 to MDOT Signal Operations to request a study for any electronic pedestrian device.



^{*} RECOMMENDATION BASED ON CITY OF BOULDER SAFETY EVALUATIONS AT EXISTING RRFB SITES AND OBSERVED IMPACTS TO VEHICULAR TRAFFIC OPERATIONS




Wrong Way Crashes

Partial Cloverleaf Interchange (PARCLO)

Will Mathies, P.E. Metro Region Safety Engineer

The Problem




- CONFUSION !!
- Sign's Height
- Directional Arrow

Data/Background



- Total of 110 crashes between 2005 and 2009.
 - 10 occurred at I-94 & M-3 interchange
- Total of 21 crashes at PARCLO Interchange
 - 48% occurred at I-94 & M-3 Interchange

The Solution




- Qwick Kurb
- Adjust Sign
- Pavement Markings

Results

"0" Wrong Way Crashes Since June 2012





Mini-Roundabouts

A POTENTIAL COST EFFECTIVE SOLUTION TO SAFELY ADDRESS CONGESTED INTERSECTIONS



The Problem: Lack of Resources to upgrade AWSC Intersections



- 66 AWSC intersections in Washtenaw County
- 13 intersections have warrants for a traffic signal
- Some intersections have 5 minute delay at peak
- Cost up to \$1 million for intersection improvement
- Infrastructure needs > resources


Potential Solution: Mini-Roundabouts

Not the same as U.K. mini BENEFITS OF MINI'S

- Compact Size
- Better Level of Service (LOS)
 - < 15,000 vpd</p>
- Safety; Equal to AWSC when designed correctly
- Reduced Construction Costs
- Reduction in Vehicle Emissions

CONSTRAINTS

- High Truck Traffic
- Light Volumes on Minc Street.




Textile Road at the Intersections of Hitchingham & Stony Creek Roads



Projected Outcomes



 Better LOS, reduced emissions, at a reduced cost to fit into your FY budget.






Chris Brookes
Work Zone Delivery Engineer
brookesc@michigan.gov
517-242-6486

Chuck Bergmann
Work Zone Technician
bergmannc@michigan.gov
517-388-5228

Safety Tools for Narrow Shoulders

SOA 2013-001



If the shoulder has been temporarily widen use the material as detailed in FUSP 12SP307A

Effective Oct 2013

Work Zone Shoulders on a 3R or 4R Freeway project is next to an open ditch and that distance from the edge line to hinge point is equal to 3' or less, shoulder delineation devices must be used

See WZD-126 for more information

^{*} Vertical Panels are an option. Contact the Work Zone Delivery Engineer for additional guidance.

Safety Tools












Drum Sheeting



Temporary Wet Reflective Pavement Markings





Optical Speed Bars

I-94 EB at Exit 12 (Sawyer Rd)



EB loop ramp


12 run-off-road crashes 5 years


Gary Loyola – Coloma TSC Traffic Engineer




Exit ramp is so long...
You could forget you are on a ramp.

Play video








Avg Speed 38 mph

0.12% Motorists exceeding 70 mph
0.04%
0.44% Motorists exceeding 65 mph
0.11%
1.12% Motorists exceeding 60 mph
0.32%



Senior Mobility

Kim Lariviere Strategic Highway Safety Engineer

The problem

- By 2030 20% of the population is expected to be over the age of 65.
- By 2029 all Baby Boomers will be over the age of 65.

Data/Background


- In 2012 in Michigan 17.8% of the licensed drivers were over the age of 65.
- Adults over the age of 65 account for over 20% of the fatalities.



Quest room rate: \$159 plus tax


The solution

- Collaboration
 - Senior Mobility Work Group
- Awareness
- Research
- Interstate collaboration



Results

- 20 Recommendations for Meeting the Transportation Needs of Michigan's Aging Population – (2011 ASSHTO Sweet 16 research project)
- 16 Recommendations for Meeting the Mobility Needs of Older Adults in Rural Michigan – (2012)
- 2014 North American Conference on Elderly Mobility Best Practices from Around the World – A Decade of Progress
- Michigan's Aging Driver Guide





Presented By: Dean Kanitz, P.E. – MDOT Safety Analysis Engineer

The problem

- Curves? What curves? We don't have any curves?
- Crashes? What crashes? We don't have any crashes?
- Plan? What Plan? We don't have any plan?

Data/Background


- Limited data on curves
- Overrepresentation of single vehicle crashes
- Overrepresentation of crashes on horizontal curves
- Pairing of information

The solution

- The path can only be seen one step at a time:
 - 0 No data
 - 1 Roadsoft
 - 2 Automated collection
 - Attached aggregated crash (3Yr), sign and marking data (TEST)
 - 3 Algorithm collection from framework (Curve Finder UW- Madision)

Results

- Preliminary process to identify trunkline curves with potential for safety enhancements
- Horizontal and vertical curve inventory
- Near Future Products:
 - Statewide horizontal curve inventory
 - Statewide identification of curves with potential for safety enhancements



MDOT Transportation Operations Centers



Hilary Owen
System Operations Engineer
Operations Field Services Division
Michigan Department of Transportation



4 TOCs



Detroit:

Southeast Michigan Transportation Operations Center (SEMTOC)

Port Huron: Blue Water Bridge (BWB)

Grand Rapids: West Michigan Transportation Operations Center (WMTOC)

Lansing: Statewide Transportation Operations Center (STOC)

TOC Functions and Capabilities

Traveler Information Dissemination

Traffic Management

Traffic Incidents (crashes, disabled vehicles, weather)
Construction (Work Zone) Coordination
Planned Events (sporting events, concerts, etc.)
Freeway Courtesy Patrol

Data Collection (traffic and weather)

Travel Times



Traffic Incident



Construction



Weather



MDOT ITS Devices

CCTV – Monitors freeway & weather activity (481)


- MVDS Detects rate of traffic flow (493)
- RWIS or ESS Assists winter advisory/maintenance (56)
- DMS Disseminates travel times, traffic incidents, construction & events (205)




Mi Drive Web Site

Keeping motorists safe, mobile and informed with real-time travel information

- Know before you go:
 Lane closures and traffic incidents
- Interactive maps
- Traffic camerasViews along major roadways
- Now available
 Mobile version for your phone



www.michigan.gov/drive



Traffic Signal Back Plates

Garrett Dawe, P.E.
Michigan Department of Transportation
North Region


The problem



- M-32 @ Meijer Driveway west of Gaylord
- New Traffic Signal Box Span Design
- Complaints that signals were difficult to see
- Complaints that, when behind a truck, signals were not visible


Data/Background

- MDOT is moving from diagonal spans to box spans
- Several safety benefits with box span design
- M-32 @ Meijer revealed some flaws, particularly on roads with a single through lane in each direction.
- Several rural intersections have developed new crash patterns after the box span was constructed




The solution

- * Add tethered back plates
- * Add low level signals



Results







Sign Mounted Flashing Beacons Genesee County, Michigan

- Currently have 13 Intersections
- 1 Curve
- Intersections scheduled for 2014

Wilson & Henderson



Davison & Oak



Mt. Morris & Jennings



Sign Mounted Flashing Beacons - Genesee County, MI

		Crash Frequency per Year				
T#	Intersection	2008	2009	2010	2011	2012
	Installation Year 2009					
T346	Hill & Elms	2	9	1	2	2
	Installation Year 2010					
T363	Wilson & Henderson	2	4	1	2	0
T312	Elms & Carpenter	5	8	5	5	5
T116	Grand Blanc & Morrish	2	3	2	2	5
T357	Seymour & Lennon	5	3	5	6	4
T129	Grand Blanc & Duffield	5	5	3	2	1
	Installation Year 2011					
T364	Ballenger Hwy Curves	8	5	4	6	9
	Installation Year 2012					
T369	Green & M15	4	5	7	4	2
T367	Lapeer & Oak	8	6	4	7	6
T270	Davison & Oak	3	3	4	2	6
T366	Lake & Tuscola	2	0	1	1	2
T368	Potter & Irish	2	1	1	2	5
	Installation Year 2013					
T304	Lewis & Frances	2	2	3	4	1
T370	Mt. Morris & Jennings	2	2	4	3	2
	Installation Year 2014					
T373	Morrish & Calkins	1	2	1	0	0
T151	Grand Blanc & Seymour	3	1	1	1	0
T336	Lewis & Wilson	1	3	1	1	1

Questions?